

Statement of Verification

BREG EN EPD No.: 000461

Issue 01

This is to verify that the

Environmental Product Declaration provided by:

IG Masonry Support

is in accordance with the requirements of:

EN 15804:2012+A1:2013

and

BRE Global Scheme Document SD207

This declaration is for:

Welded Masonry Support System (WMS)

Company Address

IG Masonry Support Ryder Close Cadley Hill Industrial Estate Derbyshire DE11 9EU



Emma Baker

Operator

12 September 2022

Date of this Issue

12 September 2022

11 September 2027

Date of First Issue

Expiry Date



This Statement of Verification is issued subject to terms and conditions (for details visit $\underline{\text{www.greenbooklive.com/terms}}.$

To check the validity of this statement of verification please, visit www.greenbooklive.com/check or contact us.

BRE Global Ltd., Garston, Watford WD25 9XX.

T: +44 (0)333 321 8811 F: +44 (0)1923 664603 E: <u>Enquiries@breglobal.com</u>





Environmental Product Declaration

EPD Number: 000461

General Information

EPD Programme Operator	Applicable Product Category Rules					
BRE Global Watford, Herts WD25 9XX United Kingdom	BRE Environmental Profiles 2013 Product Category Rules for Type III environmental product declaration of construction products to EN 15804:2012+A1:2013					
Commissioner of LCA study	LCA consultant/Tool					
IG Masonry Support Ryder Close Cadley Hill Industrial Estate Derbyshire DE11 9EU	Flavie Lowres/LINA v2.0					
Declared Unit	Applicability/Coverage					
1500 mm length with bracket positioned at 170mm and shelf angle of 100 mm @ 15.83 kg/unit including fixings	Product Average.					
EPD Type	Background database					
Cradle to Gate with options	ecoinvent					
Demonstra	ition of Verification					
CEN standard EN 15	5804 serves as the core PCR ^a					
Independent verification of the declaration and data according to EN ISO 14025:2010 ☐ Internal ☑ External						
(Where appropriate ^b)Third party verifier: Pat Hermon						
a: Product category rules b: Optional for business-to-business communication; mandatory	for business-to-consumer communication (see EN ISO 14025:2010, 9.4)					

Comparability

Environmental product declarations from different programmes may not be comparable if not compliant with EN 15804:2012+A1:2013. Comparability is further dependent on the specific product category rules, system boundaries and allocations, and background data sources. See Clause 5.3 of EN 15804:2012+A1:2013 for further guidance



Information modules covered

	Product		Construction		Use stage Related to the building fabric				Relat	ted to	End-of-life			Benefits and loads beyond the system boundary		
A 1	A2	А3	A4	A5	B1	B2	В3	B4	В5	В6	В7	C1	C2	C3	C4	D
Raw materials supply	Transport	Manufacturing	Transport to site	Construction – Installation	Use	Maintenance	Repair	Replacement	Refurbishment	Operational energy use	Operational water use	Deconstruction demolition	Transport	Waste processing	Disposal	Reuse, Recovery and/or Recycling potential
$\overline{\mathbf{A}}$	$\overline{\mathbf{A}}$	$\overline{\checkmark}$			$\overline{\checkmark}$	$\overline{\checkmark}$	$\overline{\mathbf{A}}$	$\overline{\mathbf{A}}$	$\overline{\checkmark}$	$\overline{\checkmark}$	$\overline{\checkmark}$					

Note: Ticks indicate the Information Modules declared.

Manufacturing site(s)

IG Masonry's welded masonry support (WMS) is manufactured at IG Masonry Support's factory

Ryder Close Cadley Hill Industrial Estate Derbyshire DE11 9EU


Construction Product

Product Description

IG Masonry Support's masonry support (WMS) is a rigid masonry support system comprised of a stainless steel angle support shelf with fixed brackets. It is designed to be secured flush to a superstructure in order to support the external facing brick work of a traditional masonry facade building.

Technical Information

Property	Value, Unit
Material	304 stainless grade






Main Product Contents

Material/Chemical Input	%
Stainless steel	95.8%
Fixing elements	4.2%

Manufacturing Process

The fabrication of Welded Masonry Support begins with the nesting process to form brackets and shelf angle sections. Once cut via laser the brackets are then folded into their unique form using a press brake. Then brackets are then welded during fabrication to the shelf angle sections. Quality checks are then conducted before product sign off. Only approved units are sent to packing and dispatch.

Process flow



Life Cycle Assessment Calculation Rules

Declared unit description

1500 mm length with bracket positioned at 170mm and shelf angle of 100 mm @ 15.79 kg/unit including fixings.

System boundary

This cradle-to-gate EPD has assessed in accordance with the modular approach as defined in EN15804:2012+A1:2013 and includes the processes covered in the manufacturing site and product stage A1 to A3 and use stages B1 to B7.



Data sources, quality and allocation

Specific primary data derived from the WMS production process in Ryder Close, Cadley Hill Industrial Estate, Derbyshire. DE11 9EU factory, have been modelled using the LINA LCA software v2.0 and the BRE LINA database v2.0.92. In accordance with the requirements of EN15804, the most current available data has been used. The manufacturer-specific data from WMS covers a period of one year (01/01/2020 – 31/12/2020). Secondary data has been obtained for all other upstream and downstream processes that are beyond the control of the manufacturer (i.e. raw material production) from the ecoinvent 3.2 database. All ecoinvent datasets are complete within the context used and conform to the system boundary and the criteria for the exclusion of inputs and outputs, according to the requirements specified in EN15804. WMS is not the only product to manufactured at the Ryder Close factory. Site wide values for energy, water and wastewater have been allocated on a mass basis. Figures for the raw materials, ancillary materials and packaging were from actual usages. Allocation of energy, water, and waste has been done according to the provisions of the BRE PCR PN514 and EN 15804.

This LCA covers the IG Masonry WMS product range. The system is available in different sizes to accommodate brick slips to achieve project design requirements. The LCA covers all of the products in the range and results for all inputs are averaged based on total output in tonnes for all products and calculated average kg/unit.

Specific UK datasets have been selected from the ecoinvent LCI for this LCA. The quality level of geographical and technical representativeness is therefore good. The quality level of time representativeness is good as the background LCI datasets are based on ecoinvent v3.2 which was compiled in 2015. Therefore, there is approximately 5-6 years between the ecoinvent LCI reference year and the time period for which the LCA was undertaken

Cut-off criteria

All processes associated with the manufacturing process and all fixings have been included. The impact of the bricks is not included in this EPD.

All inputs or outputs have been included and all raw materials, packaging and transport, energy, water use and wastes, are included, except for direct emissions to air, water and soil, which are not measured. Upstream extraction and/or processing of inputs are included within the use of the background datasets within LINA.



LCA Results

(MND = module not declared; MNR = module not declared; INA = indicator not assessed; AGG = aggregated)

WIND - Modul	io riot addiarda,	IVIII	_ 1110aa10 1	iot dociaro	a, 11 (7 t – 111	aloatol flot	accocca,	7100 - ug	igi ogatoa)
Parameters	describing e	enviro	nmental	impacts					
			GWP	ODP	AP	EP	POCP	ADPE	ADPF
			kg CO ₂ equiv.	kg CFC 11 equiv.	kg SO ₂ equiv.	kg (PO ₄) ³⁻ equiv.	kg C₂H₄ equiv.	kg Sb equiv.	MJ, net calorific value.
	Raw material supply	A1	1.38E+02	6.91E-06	8.25E-01	2.45E-01	9.01E-02	3.60E-03	1.80E+03
Product stage	Transport	A2	2.35E-01	4.33E-08	7.87E-04	2.08E-04	1.37E-04	6.20E-07	3.56E+00
1 Toduct stage	Manufacturing	А3	2.59E+00	2.25E-07	1.91E-02	4.69E-03	2.09E-03	7.42E-06	6.89E+01
	Total (of product stage)	A1-3	1.41E+02	7.18E-06	8.45E-01	2.50E-01	9.23E-02	3.61E-03	1.87E+03
Installation stage	Transport to site	A4	MND	MND	MND	MND	MND	MND	MND
	Installation	A5	MND	MND	MND	MND	MND	MND	MND
	Use	B1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Maintenance	B2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Repair	В3	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Use stage	Replacement	B4	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Refurbishment	B5	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Operational energy use	B6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Operational water use	B7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Deconstruction, demolition	C1	MND	MND	MND	MND	MND	MND	MND
End of life	Transport	C2	MND	MND	MND	MND	MND	MND	MND
End of life	Waste processing	C3	MND	MND	MND	MND	MND	MND	MND
	Disposal	C4	MND	MND	MND	MND	MND	MND	MND

GWP = Global Warming Potential; ODP = Ozone Depletion Potential; AP = Acidification Potential for Soil and Water; EP = Eutrophication Potential; POCP = Formation potential of tropospheric Ozone; ADPE = Abiotic Depletion Potential – Elements; ADPF = Abiotic Depletion Potential – Fossil Fuels;



Parameters describing resource use, primary energy										
			PERE	PERM	PERT	PENRE	PENRM	PENRT		
			MJ	MJ	MJ	MJ	MJ	MJ		
	Raw material supply	A1	3.41E+02	3.18E-02	3.41E+02	1.92E+03	9.85E+00	1.92E+03		
Product stage	Transport	A2	4.72E-02	1.76E-07	4.72E-02	3.53E+00	0.00E+00	3.53E+00		
Froduct stage	Manufacturing	А3	1.96E+01	2.33E-05	1.96E+01	8.44E+01	0.00E+00	8.44E+01		
	Total (of product stage)	A1-3	3.61E+02	3.19E-02	3.60E+02	2.00E+03	9.85E+00	2.01E+03		
Installation	Transport to site	A4	MND	MND	MND	MND	MND	MND		
stage	Installation	A5	MND	MND	MND	MND	MND	MND		
	Use	B1	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
	Maintenance	B2	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
	Repair	ВЗ	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
Use stage	Replacement	B4	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
	Refurbishment	B5	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
	Operational energy use	B6	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
	Operational water use	B7	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00		
	Deconstruction, demolition	C1	MND	MND	MND	MND	MND	MND		
End of life	Transport	C2	MND	MND	MND	MND	MND	MND		
End of life	Waste processing	СЗ	MND	MND	MND	MND	MND	MND		
	Disposal	C4	MND	MND	MND	MND	MND	MND		

PERE = Use of renewable primary energy excluding renewable primary energy used as raw materials;

PERM = Use of renewable primary energy resources used as raw materials;

PERT = Total use of renewable primary energy resources;

PENRE = Use of non-renewable primary energy excluding non-renewable primary energy resources used as raw materials; PENRM = Use of non-renewable primary energy resources used as raw materials;

PENRT = Total use of non-renewable primary energy resource



			SM	RSF	NRSF	FW
			kg	MJ net calorific value	MJ net calorific value	m ³
	Raw material supply	A1	0.00E+00	0.00E+00	0.00E+00	1.52E+00
Product stage	Transport	A2	0.00E+00	0.00E+00	0.00E+00	7.71E-04
Froduct stage	Manufacturing	A3	0.00E+00	0.00E+00	0.00E+00	2.86E-02
	Total (of product stage)	A1-3	0.00E+00	0.00E+00	0.00E+00	1.55E+00
Installation stage	Transport to site	A4	MND	MND	MND	MND
	Installation	A5	MND	MND	MND	MND
	Use	B1	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Maintenance	B2	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Repair	В3	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Use stage	Replacement	B4	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Refurbishment	B5	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Operational energy use	B6	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Operational water use	В7	0.00E+00	0.00E+00	0.00E+00	0.00E+00
	Deconstruction, demolition	C1	MND	MND	MND	MND
End of life	Transport	C2	MND	MND	MND	MND
End of life	Waste processing	С3	MND	MND	MND	MND
	Disposal	C4	MND	MND	MND	MND

SM = Use of secondary material; RSF = Use of renewable secondary fuels; NRSF = Use of non-renewable secondary fuels; FW = Net use of fresh water



			HWD	NHWD	RWD
			kg	kg	kg
	Raw material supply	A1	1.03E+02	2.50E+01	4.10E-03
Product stage	Transport	A2	1.49E-03	1.66E-01	2.45E-05
Product stage	Manufacturing	А3	2.61E-02	1.44E-01	3.36E-04
	Total (of product stage)	A1-3	1.04E+02	2.53E+01	4.46E-03
Installation	Transport to site	A4	MND	MND	MND
stage	Installation	A5	MND	MND	MND
	Use	B1	0.00E+00	0.00E+00	0.00E+00
	Maintenance	B2	0.00E+00	0.00E+00	0.00E+00
	Repair	В3	0.00E+00	0.00E+00	0.00E+00
Use stage	Replacement	B4	0.00E+00	0.00E+00	0.00E+00
	Refurbishment	B5	0.00E+00	0.00E+00	0.00E+00
	Operational energy use	B6	0.00E+00	0.00E+00	0.00E+00
	Operational water use	В7	0.00E+00	0.00E+00	0.00E+00
	Deconstruction, demolition	C1	MND	MND	MND
and of life	Transport	C2	MND	MND	MND
End of life	Waste processing	СЗ	MND	MND	MND
	Disposal	C4	MND	MND	MND

HWD = Hazardous waste disposed; NHWD = Non-hazardous waste disposed; RWD = Radioactive waste disposed



Other environmental information describing output flows – at end of life									
			CRU	MFR	MER	EE			
			kg	kg	kg	MJ per energy carrier			
	Raw material supply	A1	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
Product stage	Transport	A2	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
Froduct stage	Manufacturing	А3	0.00E+00	3.60E+00	0.00E+00	0.00E+00			
	Total (of product stage)	A1-3	0.00E+00	3.60E+00	0.00E+00	0.00E+00			
Installation	Transport to site	A4	MND	MND	MND	MND			
stage	Installation	A5	MND	MND	MND	MND			
	Use	B1	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
	Maintenance	B2	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
	Repair	В3	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
Use stage	Replacement	B4	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
	Refurbishment	B5	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
	Operational energy use	B6	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
	Operational water use	В7	0.00E+00	0.00E+00	0.00E+00	0.00E+00			
	Deconstruction, demolition	C1	MND	MND	MND	MND			
	Transport	C2	MND	MND	MND	MND			
End of life	Waste processing	СЗ	MND	MND	MND	MND			
	Disposal	C4	MND	MND	MND	MND			

CRU = Components for reuse; MFR = Materials for recycling MER = Materials for energy recovery; EE = Exported Energy



Scenarios and additional technical information

Scenarios and addi	itional technical information							
Scenario	Parameter Units Results							
B1 – Use	Once installed, there is no impact during the use phase the WMS system as it is placed behind the brick slips and cannot be accessed							
	No environmental impact	N/A	0					
B2 – Maintenance	No maintenance is required during the use phase of the WM brick slips and cannot be accessed	/IS system as it is pl	aced behind the					
	No maintenance	N/A	0					
B3 – Repair	No repair is required during the use phase the WMS system as it is placed behind the brick slips and cannot be accessed							
	No repair N/A 0							
B4 – Replacement	No replacement is required during the use phase the WMS slips. The WMS system will therefore have the same lifespa							
	No replacement N/A 0							
B5 – Refurbishment	No refurbishment is required during the use phase the WMS brick slips. The WMS system will therefore have the same li							
	No refurbishment	N/A	0					
Reference service life	The WMS system is assumed to have the same lifespan as	the building it is use	ed on					
B6 – Use of energy; B7 – Use of water	The product does not require any water or energy in use							
	Energy use	kWh	0					
	Water use	kWh	0					

References

BSI. Sustainability of construction works – Environmental product declarations – Core rules for the product category of construction products. BS EN 15804:2012+A1:2013. London, BSI, 2013.

BSI. Environmental labels and declarations – Type III Environmental declarations – Principles and procedures. BS EN ISO 14025:2010 (exactly identical to ISO 14025:2006). London, BSI, 2010.

BSI. Environmental management – Life cycle assessment – Principles and framework. BS EN ISO 14040:2006. London, BSI, 2006.

BSI. Environmental management – Life cycle assessment – requirements and guidelines. BS EN ISO 14044:2006. London, BSI, 2006.